

SUMMARY OF APPROXIMATE QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNITS	SCHEDULE I		SCHEDULE II		SCHEDULE III	
			ESTIMATE	AS BUILT	ESTIMATE	AS BUILT	ESTIMATE	AS BUILT
C-105a	Mobilization	LS	1	0	1	0	1	0
L-108a	Install #8 AWG, L-824C, 5000V, Wire	LF	12,000	0	0	0	20,000	0
L-108b	Install #6 AWG, Bare Copper Counterpoise Including Ground Rods and Terminations	LF	11,500	0	0	0	15,000	0
L-109a	Install New L-828 Constant Current Regulator, Ferroresonant Type	EA	1	0	0	0	0	0
L-110a	Install 1-2" SCH. 40 PVC Duct, Direct Earth Buried (DEB)	LF	10,500	0	0	0	14,000	0
L-115a	Install Electrical Junction Box, Complete	EA	0	0	0	0	10	0
L-125a	Remove Taxiway Edge Light, Complete	EA	0	0	0	0	124	0
L-125b	Remove Runway Edge Light, Complete	EA	47	0	0	0	0	0
L-125c	Remove Runway In-Pavement Edge Light	EA	1	0	0	0	0	0
L-125d	Install L-861T LED Taxiway Edge Light, Base Mounted	EA	0	0	0	0	183	0
L-125e	Install L-861 LED Runway Edge Light, Base Mounted	EA	47	0	0	0	0	0
L-125f	Remove PAPI System	EA	0	0	2	0	0	0
L-125g	Install L-880A LED PAPI System	EA	0	0	2	0	0	0
L-125h	Remove REIL System	EA	0	0	2	0	0	0
L-125i	Install L-849V LED REIL	EA	0	0	2	0	0	0
L-125j	Remove Runway Threshold Light	EA	16	0	0	0	0	0
L-125k	Install L-861E LED Runway Threshold Light, Base Mounted	EA	16	0	0	0	0	0

ISSUE FOR BID

THESE DRAWINGS ARE FOR BIDDING PURPOSES ONLY. THEY WERE PREPARED BY OR UNDER THE SUPERVISION OF:

BRYAN SCOT GREGORY 2006019659 8/19/19
NAME REG. NO. DATE
FOR AND ON BEHALF OF JVIATION, INC.



**KENNETT MEMORIAL AIRPORT
KENNETT, MISSOURI**

DES:Z.A.C.	ISSUE RECORD			
	NO.	BY	DATE	DESCRIPTION
DR: E.H.M.	1	BSG	8/19/19	ISSUED FOR BID
CH: C.L.G.				
APP: B.S.G.				

**RUNWAY 2/20, NAVIGATIONAL AIDS,
AND TAXIWAY A
LIGHTING REHABILITATION**

SUMMARY OF QUANTITIES

AIP PROJ. NO. 19-079C-1 JVIATION PROJ. NO. 2019.TKX.01

SHEET NAME

G005

SHEET NO.

6 of 36